				9.41	4,737.83	Rupees Four Thousand seven Hundered thirty seven,eighty three only
72	91	Providing & fixing in position anodised aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame of size 61.85*31.75mm bottom section 1.2mm thick,weight 0.695kg/m,sides and top section 1.3mm,thick,weight 0.695kg/m,shutter comprising top and bottom section of size 40mm*18mm,wall thickness 1.25mm,weight 0.417kg/m,shutter outer side 40mm*18mm,wall thickness 1.25mm,weight 0.417 kg/m,shutter interlock section 40mm*26.7mm wall thickness 1.1mm,thick,weight 0.469kg/m,the shutter mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.,providing and fixing 5.5mm,thick plainglass for shutters fitted with rubber beading all aluminium sections powered coated to a minium of 60-70 microns with exterior durable pur polyester grade powder of approved quality including cutting to required length joints mitred	sqm	3.24	4,000.00	Rupees Four Thousand Only
73	92	Applying priming coat over new wood surfaces and I wood based surfaces with white lead paint priming including preparing the surfaces after thoroughly cleaning oil,grease,dirt and foreign matter,sand preparing and knotting ready mix paint including cost of materials,labour,complete as per specifications.	sqm	35.99	100.00	Rupees One Hundered Only
74	93	Applying priming coat over new wood surfaces and I wood based surfaces with white lead paint priming including preparing the surfaces after thoroughly cleaning oil,grease,dirt and foreign matter,sand preparing and knotting ready mix paint including cost of materials,labour,complete as per specifications FIRST FLOOR	sqm	18.13	100.00	Rupees One Hundered Only

Executive Engineer
RR Nagar Division

Scanned by CamScanner

75	94	Applying priming coat over new wood surfaces and I wood based surfaces with white lead paint priming including preparing the surfaces after thoroughly cleaning oil,grease,dirt and foreign matter,sand preparing and knotting ready mix paint including cost of materials,labour,complete as per specifications.SECOND FLOOR	sqm	12.06	100.00	Rupees One Hundered Only
76	95	Providing and applying painting two coats (excluding priming coat) on new wood surface and /or wood based surface with enamel paint to give an even shade,cleaning the surface of all dirt,dust and foreign matter,sand papering including cost of materials,labour,complete as per specifications	sqm	35.99	100.00	Rupees One Hundered Only
77	96	Providing and applying painting two coats (excluding priming coat) on new wood surface and /or wood based surface with enamel paint to give an even shade,cleaning the surface of all dirt,dust and foreign matter,sand papering including cost of materials,labour,complete as per specifications. first floor	sqm	18.13	100.00	Rupees One Hundered Only
78	97	Providing and applying painting two coats (excluding priming coat) on new wood surface and /or wood based surface with enamel paint to give an even shade,cleaning the surface of all dirt,dust and foreign matter,sand papering including cost of materials,labour,complete as per specifications. second floor	sqm	12.06	100.00	Rupees One Hundered Only
79	98	KSRB 7.9:Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats or M.S square rods,or combination of M.S flats and sqare rods as per approved design,drawing including cutting steel sections and welding the same required pattern with a coat of red lead primer,cost of materials,fixtures,labour and HOM of machinery complete as per specifications. ground floor	sqm	610.00	100.00	Rupees One Hundered Only

Contractor

Executive Engineer
RR Nagar Division

Scanned by CamScanner

80	99	KSRB 7.9:Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats or M.S square rods,or combination of M.S flats and sqare rods as per approved design,drawing including cutting steel sections and welding the same required pattern with a coat of red lead primer,cost of materials,fixtures,labour and HOM of machinery complete as per specifications. First floor	sqm	756.01	100.00	Rupees One Thousand Only
				53.99	96.79	Rupees Ninty six,seventy nine paisa
81	100	KSRB 7.9:Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats or M.S square rods,or combination of M.S flats and sqare rods as per approved design,drawing including cutting steel sections and welding the same required pattern with a coat of red lead primer,cost of materials,fixtures,labour and HOM of machinery complete as per specifications.	sqm	100.00	100.00	Rupees One Hundered Only
82	101	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil,grease,dirt and other foreign matter,including cost of materials,labour,complete as per specifications.	sqm	105.30	120.00	Rupees One Hundered Twenty only
				128.68	101.76	Rupees One Hundered one seventy six paisa only
83	102	KSRB13-8.5 : Providing and fixing to wall,ceiling,and floor,low density polyethylene pipes 6.00 kgf/sq.cm working pressure 140mm outside diameter with special flange compression type fitting,wall clips,making good the wall,ceiling and floor including cost of all materials,labour charges,HOM of equipments and testing,excluding cost of fittings, complete as per specifications.	rmt	15.00	400.00	Rupees Four Hundered Only

Executive Enginee
RR Nagar Divisior

Scanned by CamScanner

		providing and laying intergal cement based waterproofing treatment including preparation of surface as required for treatment of of roofs balconies,terraces etc., constisting of i) applying and grouting a slurry coat of neat cement coat using 2.75kg/smt of cement and mixed with proprietary water proofing compound conforming to IS 2645 over the RCC slab including cleaning the surface before treatment.ii)Laying cement concrete using broken well saturated				
84	103	brickbats 25mm to 100mm size with 50% of CM 1:5 cement 43 grade and mixed with proprietary waterproofing compound confirming to IS 2645 to required slope, and treating similarly adjoining walls upto 300mm height including rounding of junction walls/slabs. The brickbats are to be flooded with standing water for two days and the dissolved brick bats are to be replaced with well burnt standard brick bats.iii) After two days of proper curing applying a second coat of cement slurry	sqm	214.05	1,000.00	Rupees One Thousand Only
85	104	Providiing and laying heavy duty cobble stones 60mm the interlock pavers using cement and course sand for manufacture of blocks of approved size shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thk sand bed(average thickness) and compacting with plate vibrator having 3 tons compaction with plate vibrater having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints final compaction of [avers surface joints into its final level, including cost of materials, labour, HOM of nachineries complete as per specifications.	sqm	264.97	1,000.00	Rupees One Thousand Only

Executive Engineer
RR Nagar Division

Scanned by CamScanner